

0531P CSR HIMMEL IN SUSPENDED CEILINGS – COMBINED

Branded worksection

This branded worksection *Template* has been developed by NATSPEC in conjunction with **CSR Himmel Interior Systems** and may be used whilst the Product Partner is licensed to distribute it. The copyright remains with NATSPEC. As with all NATSPEC worksections, it is the responsibility of the user to make sure it is completed appropriately for the project. The user should also review its applicability for local conditions and regulations. Check www.natspec.com.au for the latest updated version.

Worksection abstract

This branded worksection *Template* is applicable to suspended internal ceilings of dry construction with suspension systems attached to a supporting structure supplied by CSR Himmel. It also includes generic text for flushlined internal ceilings and external soffits dry construction with suspension systems attached to a supporting structure.

Guidance text

All text within these boxes is provided as guidance for developing this worksection and should not form part of the final specification. This *Guidance* text may be hidden or deleted from the document using the NATSPEC Toolbar or the hidden text *Hide* and *Delete* functions of your word processing system. For additional information visit FAQs at www.natspec.com.au.

Optional style text

Text in this font (blue with a grey background) covers items specified less frequently. It is provided for incorporation into *Normal* style text where it is applicable to a project.

Related material located elsewhere in NATSPEC

If a listed worksection is not part of your subscription package and you wish to purchase it, contact NATSPEC.

Related material may be found in other worksections. See for example:

- 0342 *Light steel framing* for structural ceiling framing.
- 0382 *Light timber framing* for structural ceiling framing.
- 0472 *Acoustic insulation* for acoustic insulation to walls and ceiling systems.
- 0511 *Lining* for screw-up lining to structural ceiling framing and direct fix ceilings.
- 0521 *Partitions – demountable* or 0522 *Partitions – framed and lined* for plenum baffles.
- 0574 *Window coverings* for ceiling mounting or ceiling fixed concealed track for curtains and blinds.

Material not provided by CSR Himmel

This branded worksection includes generic material which may not be provided by the Product Partner including:

- Sheet lining.
- External suspended soffits.
- Access panels.

Documenting this and related work

You may document this and related work as follows:

- Show ceiling types and coordination of combined services on reflected ceiling plans and sections.
- Show particular requirements for the sheet linings, which can be on the drawings or scheduled either in this worksection or in 0511 *Lining*. Do not duplicate.
- Detail bulkheads and curtain recesses on drawings and coordinate with 0574 *Window coverings*.

The *Normal* style text of this worksection may refer to items as being documented elsewhere in the contract documentation. Make sure they are documented.

Specifying ESD

The following may be specified using included options:

- Demountability, e.g. modular ceiling panel systems can be disassembled and re-used during tenancy fitouts.

The following may be specified by including additional text:

- Recycled material content, e.g. steel and aluminium for ceiling panels and ceiling suspension systems, recycled paper, synthetic mineral wool manufactured from slag, a waste product of steel production.
- Renewable raw materials, e.g. ceiling panels with corn or wheat starch binders, wood wool panels made from sustainable timber.
- Mineral tiles with post-consumer contents and an off-cut recycling program.
- Ceiling panels with zero or low formaldehyde emission.

- Ceiling panels with high light reflectance to improve the quality and quantity of natural lighting and thus reduce artificial lighting demands.
 - Ceiling products manufactured using processes incorporating sustainability measures, e.g. recycling of water and waste.
- Refer to the NATSPEC TECHreport TR 01 on specifying ESD.

1 GENERAL

CSR Himmel Interior Systems offer a wide portfolio of ceilings, walling, aluminium and architectural hardware products to the market, striving to distribute products that create smart spaces for life. Backed by a strong portfolio of industry leading European brands, such as OWA, Ecophon & Troldekt, Himmel brings European style and finesse to residential and commercial spaces throughout Australia, introducing the latest global trends and technologies to the interior systems market first.

1.1 RESPONSIBILITIES

General

Requirement: Provide CSR Himmel suspended ceilings, as documented.

Documented is defined in *0171 General requirements* as meaning contained in the contract documents.

The responsibility of the designer is to select a product that is:

- Appropriate for the suspended ceiling type.
- Appropriate for expected environmental conditions, e.g. for external soffits in a corrosive atmosphere and ceilings to indoor swimming pools, refer to NATSPEC TECHnote DES 010 for more information on atmospheric corrosivity.

1.2 COMPANY CONTACTS

CSR Himmel technical contacts

Website: www.himmel.com.au/Contact-Us

1.3 CROSS REFERENCES

General

Requirement: Conform to the following:

- *0171 General requirements*.

0171 General requirements contains umbrella requirements for all building and services worksections.

List the worksections cross referenced by this worksection. *0171 General requirements* references the *018 Common requirements* subgroup of worksections. It is not necessary to repeat them here. However, you may also wish to direct the contractor to other worksections where there may be work that is closely associated with this work.

NATSPEC uses generic worksection titles, whether or not there are branded equivalents. If you use a branded worksection, change the cross reference here.

1.4 STANDARDS

General

Suspended ceilings: To AS/NZS 2785.

AS/NZS 2785 specifies the minimum requirements for the design, construction, installation, maintenance and testing for suspended ceiling systems of dry construction with suspension systems attached to a supporting structure. It is intended for use in commercial, industrial and residential applications.

AS/NZS 2785 clause 3.1.2 requires that the ceiling system remain structurally sound, without maintenance for a period of 15 years. AS/NZS 2785 Appendix F (Informative) addresses material selection and performance.

The AS/NZS 2785 definitions do not include timber systems that form part of the gypsum lining standard AS/NZS 2589.

1.5 MANUFACTURER'S DOCUMENTS

Technical manuals

Website: www.himmel.com.au/Technical-Resources

1.6 INTERPRETATION

Definitions

General: For the purposes of this worksection the definitions given in AS/NZS 2785 and the following apply:

- Ceiling unit: Tile, panel, plank, strip or open grid supported within a ceiling suspended system.

Edit the **Definitions** subclause to suit the project or delete, if not required. List alphabetically.

1.7 TOLERANCES

Suspension system

Flatness, twist, winding and bow: 1.5 mm deviation from a 1.5 m straightedge placed in any position.

Sheeted or flush ceiling system

Suspension system bearing surface for flush lined ceiling: To AS/NZS 2589 Table 4.2.2.

Suspended grid system deflection: To AS/NZS 2785 Table 3.4.4.

1.8 SUBMISSIONS

Fire performance

Fire hazard properties: Submit evidence of conformance to PRODUCTS, **FIRE PERFORMANCE**, **Fire hazard properties**.

Fire-resistance level: Submit evidence of conformance to PRODUCTS, **FIRE PERFORMANCE**, **Fire-resistance of building elements**.

Operation and maintenance manuals

General: On completion, submit manufacturer's recommendations for the care and maintenance of the ceiling, and operating instructions for demounting, if applicable.

Products and materials

Type tests: Submit results as follows:

Type tests are carried out off-site. However, submission of evidence of a successful type test may be called up here for requirements specified in **SELECTIONS** or **PRODUCTS** when there are no **SELECTIONS**.

- Weighted suspended ceiling normalized level difference: To AS/NZS ISO 717.1.

The BCA cites ISO 717-1:1996 and AS/NZS 1276.1 for testing of construction required to have a certain R_w rating.

- Weighted sound absorption coefficient: To AS ISO 11654, as tested to AS ISO 354.

Prototypes

General: Provide a prototype of the ceiling system, including at least one example of each of the specified components, including services terminals.

Size: At least 10 m².

Location: [complete/delete]

Preferably show the location and extent on the drawings or nominate a room. Delete if a prototype is not required.

Samples

General: Submit samples as follows:

- Suspension system: Sections proposed for the suspension system, including suspension rods, clips, wall angles and trim.
- Ceiling material: Lining and ceiling units, with insulation, showing the extremes and mean of variation in colour, pattern, or texture of the proposed finish.
- Methods: Methods of jointing, fixing, height adjustment, retaining and removing ceiling units.

If prototypes are specified, separate samples of visible components may not be necessary.

Shop drawings

Set-out drawings: Submit proposed set-out, indicating cut ceiling units if any, before installation.

Coordinate with plenum services layouts, building structure and other factors affecting the layout.

The drawings should show the ceiling grid or building grid, or both. When choosing a grid module, consider the availability of ceiling unit sizes, and building access.

Warranties

Ceiling materials: Submit CSR Himmel's published product warranties.

Himmel provides the following warranties:

- OWA warranty: 30 years for tile and grid or 15 years for tiles or grid only.

1.9 INSPECTION

Notice

Inspection: Give notice so that inspection may be made of the following:

- The suspension system before the installation of ceiling units or lining.
- The ceiling assembly before the installation of fittings and site painting, if applicable.
- The completed ceiling.

Amend to suit the project, adding critical stage inspections required.

Hold points, if required, should be inserted here.

2 PRODUCTS

2.1 GENERAL

Product substitution

Other products: Conform to PRODUCTS, **GENERAL, Substitutions** in *0171 General requirements*.

The *0171 General requirements* clause sets out the submissions required if the contractor proposes alternative products. Refer also to NATSPEC TECHnote GEN 006 for more information on proprietary specification.

Storage and handling

Requirement: Store suspended ceiling system and components in a dry and secure storage area, unaffected by weather.

Product identification

General: Marked to show the following:

- Manufacturer's identification.
- Product brand name.
- Product type.
- Quantity.
- Product reference code and batch number.
- Date of manufacture.

Edit the list to suit the project or delete if not required.

2.2 FIRE PERFORMANCE

Fire hazard properties

Group number: To AS 5637.1.

Non-sprinklered buildings: Wall and ceiling linings must either have an *average specific extinction area* less than 250 m²/kg or a *smoke growth rate index* not more than 100 as determined by AS 5637.1.

Refer to NATSPEC TECHnote DES 020 for information on fire hazard properties.

Fire-resistance of building elements

Fire-resistance level: Tested to AS 1530.4.

Refer to NATSPEC TECHnote DES 020 for information on fire-resistance levels.

2.3 SUSPENSION SYSTEM

Proprietary system

General: As documented in the **Proprietary suspension system schedule**.

Protective coatings for steel components: To AS/NZS 2785 Table F1.

If the ceiling is installed in a corrosive atmosphere such as heavy industrial, maritime or indoor swimming pool enclosures, the protection of all steel components, especially hangers and suspension clips needs special consideration.

CSR Himmel suspension systems

General: As documented in the **CSR Himmel suspension system schedule**.

Himmel steel grid system: 24 mm flush face runners for two way exposed system.

Rondo Duo steel grid system: 24 mm flush face runners for two way exposed system.

2.4 CEILING UNITS

CSR Himmel ceiling units

General: As documented in the **CSR Himmel ceiling units schedule**.

OWA ceiling units: 15 mm thick mineral fibre tiles with a smooth, textured or perforated finish. and.

Mineral fibre tiles produced from bio-soluble mineral wool with square or shadowline tegular edge detail. For use in two way exposed suspension systems. Optional anti-microbial treatments are available for some products.

2.5 LINING

Plasterboard

Standard: To AS/NZS 2588.

Fibre cement

Standard: To AS/NZS 2908.2.

Wall and ceiling linings: Type B category 2.

Minimum thickness: 4.5 mm.

Cladding and soffit linings are manufactured as Type A Category 3, internal linings are Type B Category 2 and compressed sheets are Type A Category 5.

Sealants

Fire-resistance level sealant: Non-hardening sealant compatible with the ceiling materials and documented fire-resistance level.

Acoustic sealant: Non-hardening sealant compatible with the ceiling materials and rated to R_w 65.

Alternatives: Fire-resistance rated sealants are claimed to satisfy most acoustic properties.

3 EXECUTION

3.1 CONSTRUCTION GENERALLY

Working environment

General: Do not start work before the building is enclosed, wet work is complete and dry, and all work above the ceiling, including services, is complete.

Protection

General: Protect existing work from damage during the installation.

Partitions

General: If partitions are attached to the underside of the ceiling systems, include the partition mass in the seismic mass of the ceiling.

Stability

General: Install the ceilings level and fix to prevent looseness or rattling of ceiling components under normal conditions.

Structure-borne sound

General: Provide a ceiling system which does not amplify structure-borne sound. Provide suitable proprietary products or systems for reducing contact vibrations between structure and ceiling.

Control of movement

Abutments: Install the ceiling to allow for differential movement at abutting surfaces.

Exterior ceiling systems are subjected to additional thermal movement, due to the uncontrolled nature of the environment. The spacing of control joints should take into account these additional thermal effects.

Alignment: Align ceiling control joints with structural control joints. Do not bridge structural control joints.

Or show on the drawings. See AS/NZS 2785, clause 4.13.

Prefinishes

General: Repair damaged prefinishes by recoating.

Curtain recesses

General: Provide curtain recesses, including the following:

- Lining.
- Curtain track support.
- Accommodation for motors and cabling.

Edit and coordinate with drawings.

3.2 SUSPENSION SYSTEM

Show on the drawings the location and extent of the suspended ceiling and where appropriate the basic grid layout. See AS/NZS 2785 Appendix C. See also AS/NZS 2785 Section 4 on installation. Delete the installation clauses for materials not required for the project. Consult manufacturers for particular installation requirements for other materials.

Ceiling grid

Set-out: Align ceiling unit joints and centrelines of visible suspension members with documented grid lines. If not documented, set out with equal margins.

Support system

The suspension system may comprise hangers or struts depending on which direction the load is applied. External ceilings will be subjected to upward loads from wind actions and will therefore require strutting members, see AS/NZS 2785 Appendix A.

Give special consideration to ceilings subject to seismic actions as follows:

- If ceiling systems abut glazing, the horizontal seismic forces generated by the ceiling can damage the glazing.
- If large runs of ceilings are terminated at bulkheads, the horizontal seismic forces generated by the ceiling can cause separation between the ceiling and bulkhead if not properly designed.
- If the ceiling is terminated at a partition, design the partition for the seismic force generated by the ceiling.
- If the partition is terminated at the ceiling, design for the seismic force generated by the partition.

Support members: Install support members as follows:

- Space as required by the loads on the system and the type of ceiling.
- Allow for the installation of services and accessories, including ductwork, light fittings and diffusers.
- Provide additional back support or suspension members for the fixing of services and accessories to prevent distortion, overloading or excessive vertical deflection.
- Allow for access for maintenance of services.

Failure: Provide a ceiling system where failure of any one suspension point does not cause a progressive failure of the ceiling.

Height adjustment: Provide height adjustment with a length adjustment device at each suspension point, permitting length variation of at least 50 mm.

If particular height adjustment devices are not permitted, say so here. The use of threaded rod systems does not necessarily constitute a stronger ceiling grid system.

Grid members: If required, notch grid members at the junction with the perimeter trim to make sure the ceiling units lay flat on the perimeter trim.

Restriction: Do not attach the suspension system to the lip or flange of purlins.

If flange connections are necessary, they should be specifically designed and as close as possible to the web.

Services

Support: Conform to the following:

- If the service has not been designed to accept the ceiling load, do not fix suspension members to services (e.g. ductwork).
- If services obstruct the ceiling supports, provide bridging and suspension on each side of the services.
- Do not support services terminals on ceiling units.

Bracing

General: Provide bracing to prevent lateral movement and to resist the imposed horizontal seismic force.

Consider bracing the ceiling at concentrated load points, such as door openings and window openings, or where partitions are attached to the ceiling.

Consider bracing the ceiling at the perimeter where it abuts glazing to prevent the transfer of horizontal load to the glazing under seismic activity.

Bulkheads

General: Integrate bulkheads with the ceiling structure and brace to prevent lateral movement. If the ceiling is terminated at a bulkhead, provide for seismic requirements.

External suspended soffits

General: Support external suspended soffits on rigid members capable of carrying the loads from imposed actions. Install members to minimise any eccentricity, and carry the upward and downward loads from wind actions through to the supporting structure.

Fasteners

General: Provide concealed fasteners. If material supporting hangers is less than 3 mm thick, do not use screw fasteners.

3.3 CEILING UNITS**Installation**

Fitting: Fit ceiling units accurately and neatly, without distortion, and free from air leakage and staining.

Consult the ceiling system manufacturer if additional support and bracing is required to ceiling units which are required to carry loads from permanent actions other than their own weight.

Lock clips: If ceiling units are exposed to loads from wind actions or if required for security, insert lock clips at the junction of carrier rails and units.

Pattern and texture: Set out patterned or heavily textured materials with a consistent direction of pattern or texture, or as documented.

Service penetrations

General: Provide openings for all services elements, including light fittings, ventilation outlets, detectors, sprinklers and loudspeakers.

Repair: If services pass through ceiling grid members, provide additional grid members and support or relocate service.

Cut ceiling unit edges

General: Conceal, or finish to match prefinished edges, including at openings for services elements.

Generally only plain ceiling units or units within a random pattern should be considered for cutting.

3.4 PLASTERBOARD LINING

Delete this clause, if not applicable

Installation

Gypsum plasterboard and fibre reinforced gypsum plaster: To AS/NZS 2589.

Suspended flush ceilings: Fix using screw or screw and adhesive to ceiling members or support frame.

Multiple sheet layers

Application: Fire-resistance rated and acoustic rated ceilings.

Joints: Fill and flush up all joints and fixings in each layer and caulk up perimeters and penetrations before installing following layers. Stagger all sheet joints by minimum 200 mm.

Joints

Flush joints: Provide recessed edge sheets and finish flush using perforated paper reinforcing tape.

Butt joints: Make joints over framing members or otherwise provide back blocking.

External corner joints: Make joints over metallic-coated steel corner beads.

Control joints: Align lining control joints with structural control joints and as follows:

- Ceilings: At maximum 12 m centres.
- Control joint beads: Purpose-made metallic coated.
- Location: If possible, position joints to intersect light fixtures, vents or air diffusers.

Wet areas: Install additional supports, flashings, trim and sealants, as required.

3.5 FIBRE CEMENT LINING

Delete this clause, if not applicable.

Installation

General: Run sheets across the framing members. In flush jointed applications, stagger end joints in a brick pattern and locate them on framing members, away from the corners of large openings. Provide supports at edges and joints.

Suspended flush ceilings: Screw or screw and adhesive fix to ceiling members or support frame.

Multiple sheet layers

Application: Fire-resistance rated and acoustic rated ceilings.

Joints: Fill and flush up all joints and fixings in each layer and caulk up perimeters and penetrations before installing following layers. Stagger all sheet joints by minimum 200 mm.

Joints

Flush joints: Provide recessed edge sheets and finish flush using perforated paper reinforcing tape.

External corner joints: Make joints over metallic-coated steel corner beads.

Dry joints: Provide square edged sheet and finish with a PVC-U joining section.

Control joints: Align lining control joints with structural control joints and as follows:

- Ceilings: To divide into bays not larger than 10.8 x 7.2 m.
- Soffit linings: To divide into bays not larger than 4.2 x 4.2 m or 5.6 x 3.6 m.
- Control joint beads: Purpose-made metallic coated.
- Support: Provide framing parallel to the joint on each side. Do not fix the lining to abutting building surfaces.
- Location: If possible, position joints to intersect light fixtures, vents or air diffusers.

Wet areas: Install additional supports, flashings, trim and sealants, as required.

3.6 ACCESS PANELS

Provide for ceiling access panels where necessary for access to light fittings, sprinklers control valves and the like.

Finish

General: Match the access panels to the ceiling in appearance and performance.

Identification

General: Provide each access panel with an identification mark.

Non-demountable ceilings

General: Provide access panels supported and anchored to permit ready removal and refixing.

Reinforcement

General: Reinforce the back of the access panel to prevent warping and facilitate handling.

3.7 SMOKE RESERVOIRS**General**

Material: [complete/delete]

Frame: [complete/delete]

Depth: [complete/delete]

Location: [complete/delete]

See BCA Spec E2.2b for design requirements for smoke reservoirs.

3.8 TRIM**General**

Trim: Provide trim at junctions with other building elements and surfaces, including walls, beams and penetrations, consistent with the materials and finishes of the ceiling system.

Accessories

General: Provide accessories as part of the proprietary ceiling system necessary to complete the installation.

Plasterboard cornices

Fixing: Mitre at corners and adhesive fix with cornice cement. Pin in place at cornice edges until adhesive sets, remove pins and fill holes.

Fibrous plaster cornices and roses

Fixing: Pin or prop in place and fix with wet gypsum plaster and scrim straps over framing members.

Alternative: Nominate fixing by the supplier.

Fire-resistance rated walls

Requirement: Seal to soffit with sealant with an equivalent fire-resistance level before fixing decorative cornices, if any.

3.9 COMPLETION

Spares

Applies mainly to demountable systems where the ceiling units are liable to suffer from handling. Suspension system members should need less replacement. Vary the quantities stated, as required.

General: Provide spare matching ceiling components, as follows, and store the spare materials on site where directed:

- Supporting system: One spare supporting member (hanger or framework member) for every 100 members or part thereof of the same type installed in the ceiling.
- Ceiling units: One spare unit for every 50 units or part thereof installed in the ceiling.
- Accessories: One spare of each type for every 50 units or part thereof installed in the ceiling.

3.10 WARRANTIES

General

Requirement: Provide warranties for materials and workmanship in the form of interlocking warranties from the supplier and the installer.

Form: Against failure of materials and execution under normal environment and conditions of use.

Warranty terms: [complete/delete]

Period: [complete/delete]

Consult or negotiate with manufacturers for warranty terms and period, and specify only such terms as are actually available. Warranty terms: State requirements, if any, additional to those in the worksection, for each relevant item.

4 SELECTIONS

Schedules are a way of documenting a selection of proprietary or generic products or systems by their properties. Indicate their locations here and/or on the drawings. Refer to NATSPEC TECHnote GEN 024 for guidance on using and editing schedules.

4.1 GENERAL

Suspended ceiling performance schedule

The performance values apply to the complete ceiling assembly.

Document sound insulation properties by appropriate quantities and using the terms, symbols and units.

Property	A	B	C
Additional structural design actions			
Fire hazard properties: Group number			
Fire-resistance level (FRL)			
Weighted suspended ceiling normalized level difference ($D_{n,c,w}$)			
Weighted sound absorption coefficient (α_w)			

A, B, C: These designate each instance or type or location of the item scheduled. Edit to align with the project's codes or tags. Edit codes in the **Schedule** to match those on drawings.

Additional structural design actions: See AS/NZS 2785 clause 3.2. Document only those actions additional to those given in the *0171 General requirements* worksection.

- Suspended ceilings designed in conformance with AS/NZS 2785 only cover non-trafficable ceiling systems. If the plenum or roof space will be accessible for maintenance personnel on temporary or permanent walkways, make appropriate provision here and, if necessary, on the drawings. Document the imposed loadings for the supporting framework of access panels and loading from access ladders. Document the supporting framework and any structures e.g. catwalks, under the appropriate worksection e.g. *0342 Light steel framing*.

- For earthquake mass of the ceiling, see AS/NZS 2785 clause 3.3.4.2.

Consider other actions e.g. from ductwork, bulkheads, equipment, not carried independently of the ceiling system.

Group number: Refer to BCA Spec C1.10.

Fire-resistance level: Refer to AS/NZS 2785 clause 3.5.

Acoustic performance: Refer to NATSPEC TECHnote DES 027 for information on impact sound insulation and NATSPEC TECHnote DES 032 for information on airborne sound insulation.

Weighted sound absorption coefficient: AS ISO 11654 documents the method to convert sound absorption into a single number. It can be used for routine applications but not appropriate for products in a qualified environment requiring acoustical design by expertise.

WHS considerations

For guidance on occupational noise management, refer to the AS/NZS 1269 series of standards.

4.2 SUSPENSION SYSTEM

Proprietary suspension system schedule

Property	A	B	C
Product			
Material			
Basic grid (l x b) (mm)			
Wall angle trim			
Finish/colour			

A, B, C: These designate each instance or type or location of the item scheduled. Edit to align with the project's codes or tags.

Edit codes in the **Schedule** to match those on drawings.

Do not use this schedule if a full proprietary ceiling system is specified.

Product: Nominate the product suitable for flush set ceilings or ceiling units.

Material: Aluminium, zinc-coated steel, aluminium/zinc-coated steel, or stainless steel.

Wall angle trim: Plain angle, shadow angle. Use manufacturer's descriptions.

CSR Himmel suspension system schedule

Property	A	B	C
Product			
Material			
Basic grid (l x b) (mm)			
Main runner			
Cross runner			
Spline			
Wall angle trim			
Accessories			
Finish/colour			

A, B, C: These designate each instance or type or location of the item scheduled. Edit to align with the project's codes or tags.

Edit codes in the **Schedule** to match those on drawings.

Product: Select from the following:

- Himmel grid system.
- Rondo Duo grid system.

Material: Steel.

Main runner: Select from the product range as appropriate.

Cross runner: Select from the product range as appropriate.

Spline: Select from the product range as appropriate.

Accessories: Select from the product range as appropriate.

Wall angle trim: Select from the product range as appropriate.

4.3 CEILING UNITS

CSR Himmel ceiling units schedule

Property	A	B	C
Product			
Type			
Size (mm)			
Thickness (mm)			
Colour			
Edge detail			

A, B, C: These designate each instance or type or location of the item scheduled. Edit to align with the project's codes or tags.

Edit codes in the **Schedule** to match those on drawings.

Product: Select from the following:

- OWA mineral fibre tiles.

Type: Select from the following:

- OWA Alto: NRC – 0.65, CAC – 33 to 35 dB.
- OWA Sandila Micro: NRC – 0.70, CAC – 33 to 35 dB.
- OWA Sinfonia: NRC – 0.85, CAC – 35 to 39 dB.
- OWA Sinfonia with Humancare: NRC – 0.85, CAC – 35 to 39 dB.
- OWA Finetta: NRC – 0.70, CAC – 33 to 35 dB.

Edge detail: Select from the following:

- Square (SQ).
- Shadowline tegular (SLT).
- Kerfed, bevelled and cut back (SKB).
- Shadowline tegular (SLT).
- Shiplap (AK).

4.4 LINING

Sheet lining schedule

Property	A	B	C
Location			
Material			
Thickness: Plasterboard (mm)			
Thickness: Fibre cement (mm)			
Grade: Plasterboard			
Configuration			
Level of finish to AS/NZS 2589: Plasterboard			
Lining trim: Re-entrant corners			
Lining trim: Salient angles			
Plasterboard cornice: Size			
Plasterboard cornice: Profile			
Plasterboard cornice: Fire-resistance level			

Property	A	B	C
Fibrous plaster cornice: Product			
Fibrous plaster cornice: Profile			
Fibrous plaster rose: Product			
Fibrous plaster rose: Pattern			
Control joint			
Access panels			

A, B, C: These designate each instance or type or location of the item scheduled. Edit to align with the project's codes or tags. Edit codes in the **Schedule** to match those on drawings.

Location: e.g. bulkheads, fire-resisting ceiling, room type or identifier, or use lining designation on drawings or in a **Finishes schedule**.

Grade – Plasterboard: AS/NZS 2588 defines four grades by performances requirements:

- Standard.
- Bracing.
- Water resistant.
- Fire resistant.

Configuration: e.g. Single or Double layer. Note thickness of each layer.

Level of finish to AS/NZS 2589 – Plasterboard:

- Level 3: For concealed surfaces.
- Level 4: Default level for gypsum lining unless specified otherwise.
- Level 5: For gloss or semi-gloss paint finish.

Plasterboard cornice: Size 55 mm, 75 mm or 90 mm. Select profile.

Fibrous plaster cornice and roses: Usually heritage revival profiles.

Control joint: Nominate a product.

Access panels: Proprietary item, nominate size and purpose.

REFERENCED DOCUMENTS

The following documents are incorporated into this worksection by reference:

AS ISO 354	2006	Acoustics - Measurement of sound absorption in a reverberation room
AS ISO 717		Acoustics - Rating of sound insulation in buildings and of building elements
AS/NZS ISO 717.1	2004	Airborne sound insulation
AS 1530		Methods for fire tests on building materials, components and structures
AS 1530.4	2014	Fire-resistance tests for elements of construction
AS/NZS 2588	1998	Gypsum plasterboard
AS/NZS 2589	2017	Gypsum linings - Application and finishing
AS/NZS 2785	2000	Suspended ceilings - Design and installation
AS/NZS 2908		Cellulose-cement products
AS/NZS 2908.2	2000	Flat sheets
AS 5637		Determination of fire hazard properties
AS 5637.1	2015	Wall and ceiling linings
AS ISO 11654	2002	Acoustics - Rating of sound absorption - Materials and systems

The following documents are mentioned only in the **Guidance text**:

AS/NZS 1269		Occupational noise management
AS/NZS 1276		Acoustics - Rating of sound insulation in buildings and of building element
AS/NZS 1276.1	1999	Airborne sound insulation
BCA Spec C1.10	2016	Fire resistance - Fire hazard properties
NATSPEC DES 010	2015	Atmospheric corrosivity categories for ferrous products
NATSPEC DES 020	2011	Fire behaviour of building materials and assemblies
NATSPEC DES 027	2016	Impact sound insulation
NATSPEC DES 032	2014	Airborne sound insulation
NATSPEC GEN 006	2007	Product specifying and substitution
NATSPEC GEN 024	2015	Using NATSPEC selections schedules
NATSPEC TR 01	2018	Specifying ESD
ISO 717		Acoustics - Rating of sound insulation in buildings and of building elements
ISO 717-1	1996	Airborne sound insulation